BRUHATH BANGALORE MAHANAGARA PALIKE,
DASARAHALLI ZONE
Office of the Executive Engineer Dasarahalli Division

Schedule - B

BBMP/2021-22/OW/WORK_INDENT48222

NAME OF WORK: Improvements to drains and Providing Asphalting to roads at Bhuvaneshwari nagara 8th main and Surroundings in ward no 14 Bagalagunte.

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor Sri SHIVALINGAIAH SATISH	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation by manual means for roads, drains & similar works in ordinary soil invoiving , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods complete as per the specification & as per direction of Engineer-in-charge of the work	Cum	819.76	137.8	Rupees One Hundred Thirty Seven and Eighty Paise Only
2	Compaction of original ground with maximum of 6 passes of 8 to 10 tonnes power roller including filling in depression occuring during rolling including cost of all labour, HOM of machinery complete as per the specification & as per direction of Engineer-in-charge of the work	Sqm	4098.80	6.36	Rupees Six and Thirty Six Paise Only
3	Providing, laying, spreading and compacting cushed stone aggregates of granite / trap I basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed materials by tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve thedesired density complete as per the specification & as per direction of Engineer-in-charge of the work	Cum	819.76	1900.0	Rupees One Thousand Nine Hundred Only

Signature of the Contractor,

Executive Engineer,
Dasarahalli Division.

Scanned with CamScanner

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor Sri SHIVALINGAIAH SATISH	
				In Figures (Rs.)	In Words (Rs.)
4	Providing and applying primer coat with bitumen emulsion on prepared surface of granular base including clearing of road surface and spraying primer at the rate of 0.60 kg l sqm using mechanical means complete as per the specification & as per direction of Engineer-in-charge of the work	Sqm	4098.80	33.92	Rupees Thirty Three and Ninety Two Paise Only
5	Providing and laying dense graded bituminous macadam using crushed aggregates of specified grading, premixed with VG30 grade bituminous binder and, transporting the hot mix to work site, laying to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH table 500-10 complete in all respects complete as per specifications.. MORTH Specification No. 507 - using 40/60 TPH capacity H.M.P. with Mechanical paver Gr-II (50 mm to 75 mm) with 4.5 % VG-30 Bitumen complete as per the specification & as per direction of Engineer-in-charge of the work	Cum	204.94	7000.0	Rupees Seven Thousand Only
6	Cleaning the existing black topped surface with brooms, soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries complete as per specifications. complete as per the specification & as per direction of Engineer-in-charge of the work	Sqm	14157.00	5.3	Rupees Five and Thirty Paise Only
7	Providing and applying tack coat using 80/100 grade bitumen(VGIO) on the prepared black topped surfaces at 2.5 kg per 10sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM of machineries complete as per specifications.MORTH	Sqm	14157.00	12.72	Rupees Twelve and Seventy Two Paise Only

Signature of the Contractor,

Executive Engineer,
Dasarahalli Division,

Scanned with CamScanner

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor Sri SHIVALINGAIAH SATISH	
				In Figures (Rs.)	In Words (Rs.)
8	KSRRB M500-19. Providing and laying bituminous concrete 40 mm thick with hot mix plant, using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 500.9 complete in all respects complete as per specifications. Clause 507 of MORTH V Version as per IRC SP-53-2015,do-Using 40-60 TPH Capacity HMP With Mechanical Paver Grading II (30-45mm) with 5.4% of Modified bituminous binder consisting of 4.97% of VG-30 bitumen (60/70 grade) and 0.43% of plastomeric thermoplastics (Waste Plastic) complete as per the specification & as per direction of Engineer-in-charge of the work	Cum	566.28	8515.0	Rupees Eight Thousand Five Hundred Fifteen Only
9	Loading and Unloading of Stone Boulder / Stone aggregates /Sand/ Kanker / Moorum. KSRRB M100-1 : Placing tipper at loading point, loading with front end loader,dumping, turning for return trip, excluding time for haulage and return trip complete as per the specification & as per direction of Engineer-in-charge of the work	Cum	819.76	57.0	Rupees Fifty Seven Only
10	Cost of Haulage Excluding Loading and Unloading complete as per the specification & as per direction of Engineer-in-charge of the work	km	819.76	25.6	Rupees Twenty Five and Sixty Paise Only

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

Signature of the Contractor,

Executive Engineer,
Dasarahalli Division,

Scanned with CamScanner